

STATE OF KANSAS
CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-20,597-00-01

LEASE NAME CROW

WELL NUMBER 1

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 5 TWP. 24 RGE. 8W (E) or (W)

COUNTY Reno

Date Well Completed _____

Plugging Commenced 12-18-03

Plugging Completed 12-22-03

RECEIVED

JAN 07 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

CLINTON PRODUCTION, INC.

OPERATOR _____

ADDRESS 330 N. Armour Wichita, Kansas 67206

PHONE (316) 684-7996 OPERATORS LICENSE NO. 5585

Character of Well ENHR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on _____ (date)

Jack Luthi (KCC District Agent's Name).

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4143'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		<u>Sand</u>	<u>304</u>	8-5/8"	264'	None
		<u>2nd</u>	<u>3830</u>	4-1/2"	3830'	2630'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from _____ feet to _____ feet each sack. Plugged off bottom with sand to 3400' and 4 sacks cement. Cut pipe loose @2630', pulled up to 1350', pumped 10 sacks gel, 35 sacks cement, pulled up to 800', pumped 35 sacks cement, pulled up to 315' and circulated 130 sacks cement, 60/40 pos. 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Clinton Production, Inc.

State of Kansas County of Rice, SS.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of January, 20 04

My Commission Expires: _____

