

E OF KANSAS  
E CORPORATION COMMISSION  
S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-167-21,525-40-00

LEASE NAME Meharg "A"

WELL NUMBER 6

330 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 16 TWP. 15 RGE. 13W (E) or (W)

COUNTY Russell

Date Well Completed 10-1-1980

Plugging Commenced 12-23-03

Plugging Completed 12-26-03

RECEIVED

JAN 07 2004

KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

OPERATOR GRADY BOLDING CORPORATION

ADDRESS P.O. Box 486 Ellinwood, Kansas 67526

PHONE (620) 564-2240 OPERATORS LICENSE NO. 7383

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on \_\_\_\_\_ (date)

Herb Deines (KCC District Agent's Name).

ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3381'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		<u>Sand</u>	<u>570</u>	<u>8-5/8"</u>	<u>570'</u>	<u>None</u>
		<u>Red</u>	<u>3380</u>	<u>5-1/2"</u>	<u>3380'</u>	<u>2300'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each sack. Plugged off bottom with sand to 3275' and 5 sacks cement. Cut 5-1/2" casing loose #2300 ft., pulled up to 1450', pumped 300# hulls with 100 sacks cement, pulled up to 850', pumped 40 sacks cement with 100# hulls, pulled up to 250 ft. and circulated 65 sacks cement to surface, 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Grady Bolding Corporation

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of January, 20 04

[Signature]  
Notary Public

My Commission Expires:

