

STATE OF KANSAS
CORPORATION COMMISSION
5. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,464-00-00

LEASE NAME IVY

WELL NUMBER 1

3630 Ft. from X^N Section Line

4290 Ft. from X^W Section Line

SEC. 18 TWP. 22 RGE. 11W (E) or (W)

COUNTY Stafford

Date Well Completed 10-2-1987

Plugging Commenced 12-29-03

Plugging Completed 12-30-03

JAN 07 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

OPERATOR L.D. DRILLING, INC.

ADDRESS 7 SW 26th Avenue Great Bend, Kansas 67530

PHONE (620) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on 11-12-03 (date)

Richard Lacey (KCC District Agent's Name)

ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3645'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		<u>Surf</u>	<u>344</u>	<u>8-5/8"</u>	<u>344'</u>	<u>None</u>
		<u>Base</u>	<u>3636</u>	<u>5-1/2"</u>	<u>3636'</u>	<u>2020'</u>
		<u>C.B.T.</u>	<u>3620</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet surface. Plugged off bottom with sand to 3420' and 5 sacks cement. Cut pipe loose @2020'. Pulled 5-1/2" up to 600', pumped 10 sacks gel, 50 sacks cement with 100# hulls, pulled up to 370', pumped 50 sacks cement and 100# hulls, pulled up to 40' and circulated 25 sacks cement, 60/40 pos. 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: L.D. Drilling, Inc.

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 6th day of January, 2004

[Signature]
Notary Public

My Commission Expires:

