

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-21597-00-01
Spot: SENENW Sec/Twnshp/Rge: 9-22S-12E
3998 feet from S Section Line, 3204 feet from E Section Line
Lease/Unit Name: LUTHI H Well Number: 3
County: GREENWOOD Total Vertical Depth: 1817 feet

Operator License No.: 5193
Op Name: BARNARD, R.L. D/B/A BARNARD OIL O
Address: PO BOX 535 907 S 3RD
MADISON, KS 66860

Production Casing Size: 4.5 feet: 1817
Surface Casing Size: 8.625 feet: 82

\$59⁰⁵

Well Type: EOR UIC Docket No: E19904.1 Date/Time to Plug: 12/01/2003 8:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: GEORGE SAGE Company: SAGE, LARRY GEORGE Phone: (316) 437-6103

Proposed Plugging Method: 50' CEMENT PLUG AT 1750', 50' CEMENT PLUG AT 800', 150' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2003 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

PUMPED 5 SACKS CEMENT AT 1725' THROUGH TUBING, PULLED TUBING OUT. SHOT CASING AT 653' PARTED CASING AT 14', RAN TUBING BACK IN AT 650', PUMPED 17 SACKS CEMENT. PULLED TUBING OUT, SHOT CASING AT 150', RAN TUBING IN, PUMPED 1 SACK GEL AND 1 SACK HULLS AND 58 SACKS CEMENT TO SURFACE.

RECEIVED
KCC
JAN 06 2004
KCC WICHITA

RECEIVED
KCC
JAN 2 2004
Chanute KS

Remarks: CORRECTED TO GPS LOCATION

Plugged through:

District: 03

Signed Mike Heffern by SH
(TECHNICIAN)

INVOICED

DATE 1-6-04
INV. NO. 2004061029