

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21214-00-00
Spot: SENWNW Sec/Twnshp/Rge: 13-31S-40W
4030 feet from S Section Line, 4030 feet from E Section Line
Lease/Unit Name: BOND G U Well Number: 3HI
County: MORTON Total Vertical Depth: 2642 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

Production Casing Size: 5.5 feet: 2641 WITH 450 SX CMT
Surface Casing Size: 8.625 feet: 551 WITH 300 SX CMT

8582

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/17/2003 10:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: JOE EUDEY Company: BP AMERICA Phone: (620) 356-6955

Proposed Plugging Method: PUMP 500# HULLS. FILL 5 1/2" WITH CMT. CIRCULATE TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/17/2003 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


BP TD 2640'. PERFS AT 2426-64, 2504-24, 2507-78, 2604-34'. PUMP 500# HULLS MIXED WITH 355 SX CMT. PRESSURE TO 300 PSIG & SHUT IN. FILLED 5 1/2" FROM TOP TO BOTTOM. PUMP 18 SX CMT DOWN BACKSIDE. PRESSURE TO 300 PSIG & SHUT IN.

RECEIVED
JAN 08 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 2% CC BY HALLIBURTON. NO CASING RECOVERED

Plugged through: CSG

District: 01



Signed Jim Holland
(TECHNICIAN)

INVOICED
DATE 1-8-04
INV. NO. 2004061035

Form