

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22956-00-00
Spot: N2N2NWSE , Sec/Twnshp/Rge: 24-9S-24W
2510 feet from S Section Line, 1970 feet from E Section Line
Lease/Unit Name: NICKELSON Well Number: 24-1
County: GRAHAM Total Vertical Depth: 4052 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: RFD 1, 1889 200 AVENUE
PENOKEE, KS 67659

Surface Casing Size: 8.625 feet: 216

131⁷²

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/03/2004 9:00 AM
Plug Co. License No.: 30076 Plug Co. Name: ANDERSON, ANDY DBA A & A PRODUCTION
Proposal Rcvd. from: DARREL ANDERSON Company: ANDERSON, ANDY DBA A & A PR Phone: (785) 421-6266

Proposed Plugging Method: Order 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE
Date/Time Plugging Completed: 01/03/2004 11:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2150' w/25 sxs.
2nd. Plug at 1250' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40'w/10 sxs.
Rathole with 15 sxs.

RECEIVED
JAN 08 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

INVOICED

DATE 1-8-04
REV. NO. 2004061043

Form CP-2/3

JAN 06 2004