

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22424-00-00
Spot: W2SWNE Sec/Twnshp/Rge: 19-31S-37W
1980 feet from N Section Line, 2310 feet from E Section Line
Lease/Unit Name: HJV FULK A Well Number: 1
County: STEVENS Total Vertical Depth: 6100 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 6098 WITH 170 SX CMT
Surface Casing Size: 8.625 feet: 1742 WITH 525 SX CMT

#19825

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/15/2003 9:30 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY ESCOBEDO Company: EAGLE WELL SERVICE Phone: (620) 544-6204

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PLUG AT 1770' WITH 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/15/2003 3:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 6056'. PERFS AT 5964-66'. PUMP 200# HULLS WITH 20 SX CMT. DISPLACE WITH 120 BBL MUD. PRESSURE CASING TO 500 PSIG & SHUT IN. 1ST PLUG PULL OUT OF HOLE TO 1800'. CIRCULATE HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE TO 650'. CIRCULATE HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

RECEIVED
JAN 08 2004
KCC WICHITA

Remarks: USED CLASS A CMT BY PHIL DOLLAR OILFILED SERVICES. RECOVERED 2782' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
DEC 22 2003
KCC Dodge City

Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 1-8-04
INV. NO. 2004061033

Form CP 2/3