

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00122-00-02
Spot: NENE Sec/Twnshp/Rge: 7-33S-33W
4620 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: MARCH Well Number: 1
County: SEWARD Total Vertical Depth: 1573 feet

Operator License No.: 31983
Op Name: NICHOLS FLUID SERVICE, INC.
Address: 316 INDUSTRIAL PARK AVE.
LIBERAL, KS 67901

Production Casing Size: 4.5 feet: 1060 CIRCULATE TO SURFACE
Surface Casing Size: 8.625 feet: 1573 WITH 200 SX CMT

\$51¹²

Well Type: SWD UIC Docket No: D19019.0 Date/Time to Plug: 12/16/2003 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DANNY Company: NICHOLS FLUID SERVICE Phone: (620) 624-5582

Proposed Plugging Method: PUMP 200# HULLS AND FILL 4 1/2" WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/16/2003 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 1344'. PERFS AT 1090-1170'. PUMPED 250# HULLS AHEAD & 100# HULLS MIXED WITH CMT. PUMPED 100 SX CMT DOWN 4 1/2" @ 100 PSIG. SHUT DOWN. RIG UP TO BACKSIDE & IMMEDIATELY PRESSURED TO 500 PSIG. REMOVED VALVE ON 4 1/2". FLUID @ 80'. FILLED 4 1/2" WITH CMT. CASING STAYED FULL.

RECEIVED
JAN 08 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland
(TECHNICIAN)

INVOICED
DATE 1-8-04
20040.161037

Form CP-13