

15-167-22946-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: ~~1~~-167-22946-00-00  
Spot: S2NWSW Sec/Twnshp/Rge: 36-15S-13W  
1650 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: MARY SELLENS Well Number: 5  
County: RUSSELL Total Vertical Depth: 3367 feet

Operator License No.: ~~6627~~ 101  
Op Name: PROSPECT OIL & GAS CORP  
Address: ~~PO BOX 837~~ KCC Fee Fund  
RUSSELL, KS 67665

Production Casing Size: 5.5 feet: 3360 w/120 sxs cmt  
Surface Casing Size: 8.625 feet: 606 w/230 sxs cmt

#0

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/30/2003 1:00 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/30/2003 4:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 500' - 875' - 1650'.  
Swaged to 5 1/2" - mixed and pumped 100 sxs cement with 500# hulls.  
Circulated cement up 8 5/8".  
Shut in and continued cementing with 200 sxs cement.  
Max. P.S.I. 500#. S.I.P. 100#.

THIS IS A KCC FEE FUND PLUGGING.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 07 2004  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

INVOICED  
DATE 1-8-04  
INV. NO. 2004061039

Form CP-2/3

JAN 02 2004

PROSPECT OIL & GAS CO  
RUSSELL KS 67665

36-15 -13W  
C S/2 NW SW

#5 MARY SELLENS

site: 4 N & 2-1/2 W OF BEAVER KS      city: RUSSELL      API 15-167-22946  
contr: EMPHASIS OIL OPER      field: TRAPP  
oper: BRAD HUTCHINSON

lr      spd      drig      card      last  
date 11/26/90      date 11/26/90      comp 12/04/90      issued 06/24/91      revised 06/24/91


ELV: 1895 KB, 1890 GL SMP	IP status:
tops.....depth/ocm:	OIL, P 15 BO & 30 BWP, ARB 3360-3367,
ANH.....857 +1038	CSG: 8-5/8" 606 / 230 SX, 5-1/2" 3360 / 120 SX
TOP.....2770 -875	NO CORES
HEEB.....3007 -1112	DST (1) 3334-3358 (PENN, ARB), / 30-30-30-30, (1ST
TOR.....3024 -1129	OP) WB THRU-OUT, (2ND OP) NB, REC 15' SLI OCM, W /
DOUG.....3040 -1145	SOME SPTS OIL ISIP 362# FSIP 210# IFF 33# -33#
BR LM.....3088 -1193	FFP 42# -42#
LANS.....3098 -1203	DST (2) 3333-3367 (PENN, ARB), / 45-45-45-45, FB
BKC.....3335 -1440	THRU-OUT, REC 75' HOCM, 180' MO ISIP 1092# FSIP
ARB.....3354 -1459	1075# IFF 92# -101# FFP 126# -143#
RTD.....3367 -1472	TRGT ZN: ARB, PTD 3395 (ARB), MICT - CO, (ARB OH),
	AC 250 GAL (15% NE), SO, SET 2-3/8" TBG AT 3350,
	POP, P 15 BO & 30 BWP (GR 38) 1/20/91

COPYRIGHT 1990  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS