

15-167-21550-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21550-00-00
Spot: S2SESW Sec/Twnshp/Rge: 6-14S-14W
330 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: JOHNSON Well Number: 1
County: RUSSELL Total Vertical Depth: 3333 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3332
Surface Casing Size: 8.625 feet: 234 w/165 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2003 1:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2003 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 450' - 930' - 1600'.
TIH with tubing to 1650' - tied onto and circulated cement with 120 sxs cement and 500# hulls.
POOH. Swaged to 5 1/2" and pumped to pressure with 100 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.
Hooked up to the annulus and pumped 20 sxs cement.
S.I.P. 400#.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 07 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

JAN 02 2004

CRUDE OIL PRODUCERS
 BOX 119 MUNJOR ROUTE #1 JOHNSON 6-14-14W
 HAYS, KS 67601 SW SW SE
 CONTR REVLIN DRILLING INC CITY RUSSELL C S¹/₂ SE - SW

GEOL _____ FIELD GORHAM

E 1897 KB CM 12/5/80 CARD ISSUED 9/17/81 IP P 14 BOPD
1892 GL 15-167-21,550 LKC-INTV NA
 API ARB-INTV NA

	+	+
	+	+
	+	+

SMP	TOPS	DEPTH	DATUM.
TOP		2784	- 887
KH		2868	- 977
QH		2929	-1032
HEEB		3070	-1113
TOR		3030	-1133
LKC		3060	-1169
B KC		3270	-1373
ARB		3323	-1426
RTD		3333	-1436

8-5/8" 234/165sx, 5¹/₂" 3332
 DST (1) 3076-3172(LKC)/30-30-30-30,
 420'GIP, REC 300'GSY OCM, SIP 753-
 732#, FP 97-107/151-162#, BHT 102°
 MICT - CO, PF (ARB) INTV NA, SWB DWN
 W/GSO, PF (LKC) INTV NA, SWB DWN W/GSO,
 POP, P 14 BOPD 3/16/81, TIGHT HOLE -
 NO OTHER INFO TO BE RELEASED AT
 PRESENT - WILL RELEASE INFO WHEN
 AVAILABLE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS