

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21525-00-00
Spot: SWSESE , Sec/Twnshp/Rge: 16-15S-13W
330 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: MEHARG A Well Number: 6
County: RUSSELL Total Vertical Depth: 3381 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

Production Casing Size: 5.5 feet: 3380 125 SX CMT
Surface Casing Size: 8.625 feet: 570 250 SX CMT

#109⁸⁸

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/26/2003 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (316) 938-2537

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 10% gel and hulls.
Plug while pulling casing.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 12/26/2003 11:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

Sanded to 3275' and spotted 5 sxs cement with dump bailer.
Shot casing loose at 2300' and pulled to 1450'.
Mixed and pumped 100 sxs cement with 300# hulls.
Pulled casing to 850' and pumped 40 sxs cement with 100# hulls.
Pulled casing to 250' and circulated cement with 65 sxs.
Pulled casing with cement at surface.


RECEIVED
JAN 08 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-8-04

INV. NO. 2004061034

JAN 06 2004

0331060
 WMA
 WMA

ISERN-SCHULTZ OIL & GAS INC

BOX 486
 ELLINWOOD, KS 67526

#6 MEHARG "A"

16-15-13W
 SW SE SE

CONTR WOODMAN & IANNITTI

CTY RUSSELL

GEOL

FIELD TRAPP

E 1880 KB CM 8/20/80

CARD ISSUED

10/30/80

IP P 30 BO & 188 BWP

API

15-167-21,525

ARB 3338-3340

| | | |
|--|--|--|
| | | |
| | | |
| | | |

| LOG | TOPS | DEPTH | DATUM |
|------|------|-------|-------|
| SC | | 830 | +1050 |
| TOP | | 2750 | - 870 |
| HEEB | | 2982 | -1102 |
| TOR | | 3000 | -1120 |
| LKC | | 3058 | -1178 |
| ARB | | 3326 | -1446 |
| TD | | 3381 | -1501 |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

8-5/8" 570/250sx, 5 1/2" 3380/125sx
 DST (1) 2965-3020, 30-30-30-30, REC
 10' OSM, SIP 68-61#, FP 68-68/51-51#
 DST (2) 3061-3110, 30-30-30-30, REC
 30' SPKD & GCM, SIP 103-92#, FP
 82-82/72-72#
 DST (3) 3330-3341, 30-30-30-30, REC
 840' O & GCW, 170' GCW, SIP 990-940#,
 FP 82-82/440-440#, BHT 116"
 MICT - CO PF (ARB) 4/3338-3340, AC 250
 GAL, SWB 12 BFPH (30% O) 1 1/2 HRS, POP.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS