

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23631-00-00 ^{02 ajs 1/5/04}
Spot: SESWSE Sec/Twnshp/Rge: 29-12S-20W
330 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: NICHOLSON Well Number: 3
County: ELLIS Total Vertical Depth: 3911 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

Production Casing Size: 4.5 feet: 3905 100 SX CMT
Surface Casing Size: 8.625 feet: 277 155 SX CMT

#127"

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2003 12:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: KEN VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmx - 10% gel - 500# hulls.
Dakota broke in.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/05/2003 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1550' and 2150'.
TIH with tubing to 2800' - circulated cement with 200 sxs cement and 500# hulls.
POOH. Topped with 20 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Annulus full of cement.

RECEIVED
DEC 19 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

170

Signed Jay Pfeifer
(TECHNICIAN)

INVOICED Form CP-2/3

DATE 12.22.03
INV. NO. 2004060969

DEC 11 2003

replacement card

BLACK DIAMOND OIL CO
HAYS KS 67601

29-12S-20W
SE SW SE

#3 NICHOLSON

site 1-3/4 N OF ELLIS KS

cty: ELLIS

API 15-051-23631-00-02

contr: UNKNOWN

field: DISTRICT 57

geol:

fr	spd	drig	card	last
date 08/08/1990	date 10/29/1989	comp 10/30/1989	issued 08/08/1990	revised 09/22/2003

ELV: 2185 KB, 2180 GL LOG	
tops.....	depth/datum
ANH.....	1546 +639
TOP.....	3214 -1029
HEEB.....	3442 -1257
TOR.....	3464 -1279
LANS.....	3479 -1294
BKC.....	3726 -1541
MARM.....	3776 -1591
*ARB.....	3848 -1663
RTD OLD.....	3910 -1725
*SAMPLE TOP	

IP status
 OIL, P 5 BO & 200 BWPD, ARB 3858-3862 OA, 10/31/1989
 CORR & INFO REL: 9/22/2003 - ADDED WO #1 & CORR PFS
 OLD INFO: OPERATOR WAS LIBERTY OPERATIONS &
 COMP, 3 NICHOLSON, SPD 09/27/1983, 10/04/1983 8-5/8"
 277.83 / 155 SX, 4-1/2" 3894 / 100 SX, OIL, P 15 BO & 45
 BWPD, ARB 3858-3862 OA, 11/18/1983(CARD ISSUED
 10/27/1983)
 CONTR: PIONEER DRILLING
 NO CORES

COPYRIGHT 2003
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)