

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07696-00-00
Spot: W2NWSW Sec/Twnshp/Rge: 36-15S-13W
1980 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: M SELLENS Well Number: 2
County: RUSSELL Total Vertical Depth: 3360 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3352
Surface Casing Size: 10.75 feet: 160

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/06/2004 2:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed
Plugging
Method:

Orderd out 220 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/06/2004 5:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Drilled out to 750' - hit hard wood bridge - decided to P&A.
TIH with tubing to 750' - mixed and circulated cement with 75 sxs cement with 500# hulls.
POOH. Swaged onto 5 1/2" and pumped 125 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.

RECEIVED
JAN 12 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)


OKID.

STINCLAIR EQUATORIAL OIL CO #2 M. SELLENS 36-15-13W
 Contr. _____ RUSSELL _____ County _____
 E 1899 Comm 11-18-40 Comp. 12-16-40 IP 306 BOPD
 GW2 NW SW

Tops	Depth	Datum
ANHY	855	
LANS	3100	
ARB	3352	
TD	3360	

Casing
 10" 160
 5" 3352

 A/500
 1350' OIH/12 hr
 A/2000



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS