

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-07719-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 36-15S-13W  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: SELLENS Well Number: 3  
County: RUSSELL Total Vertical Depth: 3384 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S. MARKET  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3380  
Surface Casing Size: 8.625 feet: 548

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/31/2003 11:00 AM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/31/2003 2:00 PM KCC Agent: CASE MORRIS

**Actual Plugging Report:**

Perforated at 1370' - 875' - 500'.  
Ran tubing to 1400'.  
Circulated with 100 sxs 60/40 pozmix - 10% gel cement with 500# hulls.  
POOH. Pumped 130 sxs cement down 5 1/2".  
Max. P.S.I. 800#. S.I.P. 500#.

RECEIVED  
JAN 12 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04


Signed Case Morris  
(TECHNICIAN)

JAN 08 2004

SUNRAY OIL CORP #3 SELLENS 36-15-13W  
 SW NE SW  
 Contr. STICKLE DRILLING CO. RUSSELL County  
 E 1892 Comm: 3-8-50 Comp. 1-11-50 IP 170 BOPD  
 PHY POT

Tops	Depth	Datum
HFFB	2999	
BR 1 M	3082	
LANS	3092	
CONG	3350	
ARB	3358	
TD	3384	

Casing  
 8" 548 3 BOPH/5 HRS.  
 5" 3380



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS