

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21122-00-00
Spot: NENWSW Sec/Twnshp/Rge: 36-15S-13W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: MARY SELLENS Well Number: 4
County: RUSSELL Total Vertical Depth: 3393 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3393 w/125 sxs cmt
Surface Casing Size: 8.625 feet: 220 w/120 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/31/2003 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: ED POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/31/2003 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 500' - 875' - 1650'.
TIH with tubing to 1650' - mixed and pumped 100 sxs cement with 500# hulls.
Pulled up to 550' and circulated cement with 35 sxs cement.
POOH. Swaged onto 4 1/2" - pumped 30 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to the annulus and pumped 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 200#.

RECEIVED
JAN 09 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

JAN 06 2004

R.P. NIXON OPERATIONS
 207 W. 12TH ST. #4 MARY SELLENS 36-15-13W
 HAYS, KS. NE NW SW
 CONTR REVLIN DRG., INC. CTY RUSSELL

GEOL _____ FIELD TRAPP

K 1888 KB CM 12/22/77 ^{CARD}ISSUED 1/19/78 IP P 25 BOPD ± 30% W
 ARB 3344-65 OA

+	+	+
+	+	+
+	+	+

API 15-167-21,122

SMP	TOPS	DEPTH	DATUM
ANH	848	+1040	
TOP	2756	- 868	
HEEB	2993	-1105	
TOR	3009	-1121	
DOUG SH	3029	-1141	
LATAN	3077	-1189	
LKC	3085	-1197	
ARB	3340	-1452	
RTD	3393	-1505	

8-5/8" 220/120sx, 4 1/2" 3393/125sx
 NO DST'S
 MICT - PF 12/3344-47, AC 300, PF 3363-65, SWB 9 BFPH, 20% OIL, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS