

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-10034-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 6-32S-43W  
2310 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: DREYER Well Number: 1-6  
County: MORTON Total Vertical Depth: 3295 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN, LLC  
Address: 3200 FIRST PLACE TOWER  
TULSA, OK 74103

Production Casing Size: 5.5 feet: 3353  
Surface Casing Size: 8.625 feet: 599 SURFACE

*\$10709*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2003 9:00 AM  
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE  
Proposal Rcvd. from: RICKY ESCOBEDO Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: SET A CIBP @ 2900' AND DUMP 2 SX CMT ON PLUG. LOAD HOLE W/DRILLING MUD. CUT OFF 5-1/2" CASING @ 1300" ANDS SPOT A 70 SX CMT PLUG FROM 700-500'. SPOT A 10 SX PLUG FORM 40' TO SURFACE. CUT OFF CASING 3' BELOW GL AND WELD ON I.D. PLATE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/23/2003 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:


PBTD 3295'. PERFS AT 2936-3148-SQUEEZED SHUT & 3218-3284-OPEN. SET CIBP @ 2750' WITH 2 SX CMT ON TOP. FL AT 650'. CUT 5 1/2" @ 1200'. WOULD NOT COME LOOSE. CUT 5 1/2" @ 695'. 1ST PLUG CIRCULATE HOLE WITH MUD. PUMP 120 SX CMT AT 670'. GOOD CIRCULATION. PULL OUT OF HOLE WITH 5 1/2" TO 40'. TOP OF FLUID @ 300'. TRIED TO LOAD HOLE WITH MUD. WOULD NOT LOAD. TOP OF FLUID @ 100'+/-. LET BOTTOM SET OVERNIGHT. 12/23/03: TAG CMT AT 700'. PULL OUT OF HOLE TO 670'. CIRCULATE HOLE WITH MUD & PUMP 75 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE WITH TUBING TO 60'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

RECEIVED  
JAN 12 2004  
KCC WICHITA

Remarks: USED CLASS A CMT BY ALLIED. RECOVERED 695' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Jim Holland* PIRETT  
(TECHNICIAN)

INVOICED

1-12-04  
2004061052

Form CD-213