

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10036-00-00
Spot: SESENW Sec/Twnshp/Rge: 10-32S-43W
2310 feet from N Section Line, 2910 feet from E Section Line
Lease/Unit Name: DREYER Well Number: 1-10
County: MORTON Total Vertical Depth: 3276 feet

Operator License No.: 32638
Op Name: NADEL AND GUSSMAN, LLC
Address: 3200 FIRST PLACE TOWER
TULSA, OK 74103

Production Casing Size: 5.5 feet: 3276 TOC 1600'
Surface Casing Size: 8.625 feet: 658 SURFACE
#106 47

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/22/2003 9:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY ESCOBEDO Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: SEET A CIBP @ 2730' AND DUMP 2 SX CMT ON PLUG. LOAD HOLE W/DRILLING MUD. CUT OFF 5-1/2" CASING @ 1400' AND SPOT A 70 SX CMT PLUG FROM 750-550'. SPOT A CMT PLUG FROM 40' TO SURFACE. CUT OFF 3' BELOW GL AND WELD ON I.D PLATE. PER KCC.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/23/2003 11:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 3276'. PERFS AT 2755-3274'. SET CIBP @ 2655' WITH 2 SX CMT ON TOP. 1ST PLUG CIRCULATE HOLE WITH MUD & PUMP 75 SX CMT AT 650'. GOOD CIRCULATION. PULL OUT OF HOLE WITH CASING. SDON. 12/23/03: RUN IN HOLE WITH TUBING. TAG CMT AT 540'. PULL OUT OF HOLE WITH TUBING TO 90'. PUMP 30 SX CMT TO SURFACE.

RECEIVED
JAN 12 2004
KCC WICHITA


Remarks: USED CLASS A CMT BY ALLIED. RECOVERED 682' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Jim Holland
(TECHNICIAN)



INVOICED
DATE 1-12-04
INV. NO. 2004061052

Form 01-28