

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20606-00-01
Spot: NESWSW Sec/Twnshp/Rge: 24-16S-20W
990 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: MYERS G Well Number: 2
County: RUSH Total Vertical Depth: 3870 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

Production Casing Size: 5.5 feet: 3869 WITH 375 SX CMT
Surface Casing Size: 8.625 feet: 281 WITH 200 SX CMT

#125.78

Well Type: EOR UIC Docket No: E22355.1 Date/Time to Plug: 01/07/2004 12:00 PM

Plug Co. License No.: 31172 Plug Co. Name: L & M WELL SERVICING, INC.

Proposal Rcvd. from: TERRY MORRIS Company: GLM COMPANY Phone: (785) 483-2123

Proposed Plugging Method: RUN TBG. TO 3496', SPOT 25 SX & 4 SX HULLS, PULL TBG. TO 3160' SPOT 25 SX GEL & 2 SX HULLS, PULL TBG. TO 1335', CIRCULATE CEMENT TO SURFACE. HOOKUP TO BRADEN HEAD & MIX 50 SX & 2 HULLS PSI TO MAX 300#. PER KCC RULES.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/07/2004 2:22 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3631'. PERFS AT 3496-3504'. DV TOOL @ 1384' WITH 120 SX CMT. TUBING TAGGED OUT AT 3320'. PULLED TUBING TO 3310' & SPOTTED 300# HULLS MIXED IN 21 SX GEL FOLLOWED BY 25 SX CMT. PULLED TUBING TO 1400' & CIRCULATED CMT TO SURFACE WITH 110 SX CMT. PULLED TUBING OUT OF HOLE. TOPPED OFF 5 1/2" WITH 20 SX CMT. PUMPED 97 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 450 PSIG. INITIAL SHUT IN PRESSURE 200 PSIG.

RECEIVED
JAN 14 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED

Plugged through: TBG

District: 01

RECEIVED
JAN - 9 2004
KCC Dodge City

Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE

1-14-04

INV. NO.

2004061062

Form Ch 2/3
[Signature]