

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20674-00-01  
Spot: NWSESE Sec/Twnshp/Rge: 19-29S-32W  
1120 feet from S Section Line, 1070 feet from E Section Line  
Lease/Unit Name: DEWELL Well Number: 1-19A  
County: HASKELL Total Vertical Depth: 5760 feet

Operator License No.: 31666  
Op Name: COVINGTON, CURTIS F. DBA C & R PE  
Address: PO BOX 404  
SPEARMAN, TX 79081

Production Casing Size: 4.5 feet: 5646 WITH 245 SX CMT  
Surface Casing Size: 8.625 feet: 1851 WITH 785 SX CMT

*18720*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/25/2003 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 20 SX CMT. PUMP 50 BBL & 20 SX CMT AT 1850'. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE  
Date/Time Plugging Completed: 11/25/2003 5:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 5608'. DV TOOL @ 3364' WITH 470 SX CMT. PERFS AT 5088-5377'. PUMPED DOWN 4 1/2" 400# HULLS & 20 SX CMT. 1ST PLUG PUMP 50 BBL & 20 SX CMT AT 1850'. DISPLACED WITH 25 BBL MUD. SHUT IN @ 100#. LET SET 1 HOUR. 2ND PLUG PULLED TO 650' & PUMPED 50 SX CMT. 3RD PLUG PULLED TO 40' & PUMPED 10 SX CMT.

RECEIVED  
DEC 02 2003  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1183' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

*Kevin D. Strube*  
(TECHNICIAN)

INVOICED  
12-2-2003  
2004060846

Form CE 2/3  
*[Signature]*