

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-00384-00-00  
~~15-079-20258-00-00~~  
Spot: SE Sec/Twnshp/Rge: 9-23S-3W  
330 feet from S Section Line, <sup>4930' W</sup> 330 feet from ~~E~~ Section Line  
Lease/Unit Name: WARKENTINE Well Number: B-1  
County: HARVEY Total Vertical Depth: 3330 feet

Operator License No.: 5526  
Op Name: MILBURN, HAROLD J.  
Address: 7315 N. MONROE  
HUTCHINSON, KS 67502

Production Casing Size: 4.5 feet: 3329  
Surface Casing Size: 8.625 feet: 365  
#108 <sup>23</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/13/2003 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: HAROLD MILBURN Company: HAROLD J. MILBURN Phone: (620) 663-1616

Proposed Plugging Method: Sand to 3,210' and top with 4 sxs. cement. Shoot pipe off. Pull pipe to 600' and spot 35 sxs. cement. Pull pipe to 410' and circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: Plugging Operations Partially Witnessed  
Date/Time Plugging Completed: 11/13/2003 4:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,200'; and topped with 4 sxs. cement. Shot pipe off @ 1,660'. Pulled pipe to 615' and spotted 35 sxs. cement. Pulled pipe to 399' and circulated 165 sxs. cement to the surface. Cement fell 55' and operator topped with 1 yard cement on 11/14/03.  
Used 60/40 pos mix with 4% gel.

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 01 2003  
CONSERVATION DIVISION  
WICHITA, KS  
RECEIVED  
KCC DISTRICT #2  
NOV 17 2003  
WICHITA, KS

Remarks: COPELAND ACID & CEMENTING. INVOICE # 24082.

Plugged through: CSG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 12-1-03  
INV. NO. 2004060838