

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24053-00-01
Spot: NWSESE → Sec/Twnshp/Rge: 22-11S-16W
990 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: CHRISLER Well Number: 5
County: ELLIS Total Vertical Depth: 3375 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 3375 150 SX CMT
Surface Casing Size: 8.625 feet: 254 150 SX CMT

#109⁶⁹

Well Type: EOR UIC Docket No: E26201.1 Date/Time to Plug: 11/21/2003 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN SCHUMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 617-2573

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perfs at 2997'-3000'; 3142'-3144'.
F.O.Tool at 946' w/200 sxs. Wireline to 2900'. Fluid Level 1600'.
Dakota 159'-409'. Salt 1267'-1497'. Anhy.912'-948'.

Plugging Proposal Received By: PAT STAAB WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/21/2003 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Tied onto casing with a swedge and took a pump in rate of 5 bbls a minute.
Pumped 200 sxs 60/40 pozmix with 500# hulls.
Max. P.S.I. 800#. S.I.P. 300#.
Tied onto backside and pumped 5 sxs 60/40 pozmix.
Max. P.S.I. 1200#. S.I.P. 800#.

RECEIVED
DEC 09 2003
KCC WICHITA

Remarks: COPELAND ACID SERVICES AND CEMENTING.

Plugged through: CSG

District: 04

Signed

Patricia Stewart

(TECHNICIAN)

INVOICED

DATE 12-9-03

NO. 2004060878

Form CP-2/3 <

DEC 04 2003

HELMERICH & PAYNE, INC.

P.O. BOX 558

GARDEN CITY, KS 67846

#5 CHRYSLER


22-11-16W
NW SE SE

CONTR PIONEER DRILLING

CTY ELLIS

GEOL ALAN DOWNING

FIELD CHRYSLER EAST



ELV 1764 KB SPD 10/22/84 CARD ISSUED 1/24/85

IP P 16.5 BO & 35 BWPD

1759 GL
API 15-051-24,053

SHAW (TOR) 2942-2944
LKC 2997-3144 OA

MARM 3222-3224

LOG	Tops	Depth-Datum
TOP LM	2708- 944
TOR LM	2942-1178
U/LKC C	2997-1293
L/LKC C	3012-1248
LKC J	3142-1378
MARM	3222-1458
PBTD	3359-1595
RTD	3375-1611

8 5/8 " 254/150SX, 4 1/2 " 3375/150SX, FO TOOL AT 946/200SX
 DST (1) 2974-3004 (LANS C) / 30-30-30-60' REC 60' M, SIP
 151-146#, FP 50-50 / 50-50#, HP 1666-1556#
 DST (2) 3209-44 (MARM) / 30-30-30-60, REC 7' M; SIP 465-
 706#, FP 91-91 / 91-91#, HP 1917-1857#
 DST (3) 3008-61 (KC D&F, W/ STR PKR) / 30-30-30-30, REC 75'
 WM, W/ OIL SPKS, SIP 475-490#, FP 91-131 / TOOL PLUGGED,
 HP 1706-1696#
 MICT - CO, PF (LKC) 3142-44, W/ 2 SPF, AC 500G, SWB DWN,
 SO, PF (MARM) 3222-24, W/ 2 SPF, AC 500G, SWB LD, SO, PF
 (LKC) 3012-16 & 2997-3000, W/ 2 SPF, SWB DWN, SO, NAT, PF
 (TOR) 2942-44, AC 2000G, SWB DWN, GSO, T&R, POP, COM-
 MINGLED, P 16.5 BO & 35 BWPD (RR 32° AT 60°) 12/5/84

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

HELMERICH & PAYNE, INC.