

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-20225-00-01  
Spot: NE5W Sec/Twnshp/Rge: 23-14S-28W  
1980 feet from S Section Line, 3450 feet from E Section Line  
Lease/Unit Name: COBBEE UNIT Well Number: 2-3 WS  
County: GOVE Total Vertical Depth: 4465 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 4334  
Surface Casing Size: 8.625 feet: 339 w/250 sxs cmt

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2003 12:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 325 sxs of Midcon II cement and 600# hulls.  
Perfs at 390' and 2030'.  
Plug thru tubing.

Plugging Proposal Received By: BRUCE BASYE Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/12/2003 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:  
TD. 4466'. PBTd 4465'. Perforations 3931' - 3939'; 4075' - 4078'. CIBP at 4125' - 4141'.  
8 5/8" S.P. set at 339' w/250 sxs. 5 1/2" production casing set at 4334' w/1500 gallons latex.  
Perforated production casing at 390' and 2030'.  
Ran tubing to 2307' - pumped 130 sxs cement and 500# hulls.  
Pulled tubing to 1150' - pumped 65 sxs cement and 50# hulls. Cement to surface.  
Pulled tubing to surface - pumped 35 sxs cement and 50# hulls.  
Max. P.S.I. 300#. S.I.P. 0#.  
Connected to 8 5/8" surface casing - pumped 25 sxs cement.  
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED  
NOV 21 2003  
KCC WICHITA

Remarks: SWIFT SERVICES, INC. - TICKET #5952.

Plugged through: TBG

District: 04

Signed Darrel Dipman (TECHNICIAN)

INVOICED  
DATE 11-21-03  
INV. NO. 2004060812

Form CP-2/3

NOV 17 2003

CANUS PETROLEUM, BILL J. PORTER 23-14-28W  
 & DUNNE-GARDNER PET. #3 COBERLY 150'W, C.NE. SW  
 200 W. DOUGLAS, WICHITA, KS.  
 CONTR DUNNE-GARDNER CTY GOVE

GEOL \_\_\_\_\_ FIELD MISSOURI FLATS NE  
 E 2552 KB CM 7/9/74 CARD ISSUED 9/26/74 IP P 114 BOPD + 6 BWPD  
 LANS 3931-3939

+	+	+
+	+	+
+	+	+

API 15-063-20,225

LOG	TOPS	DEPTH	DATUM
ANH		1980	+ 572
B ANH		2016	+ 536
HEEB		3673	-1121
TOR		3695	-1143
LANS		3711	-1159
BKC		4006	-1454
ALI		4072	-1520
PAW		4114	-1562
FT SC		4203	-1651
CHER		4228	-1676
MISS DOL		4310	-1758
MISS OS		4364	-1812
ID		4465	-1913

8-5/8" 339/250sx, 5 1/2" 4334/1500 GAL  
 LATEX  
 DST (1) 3850-90/30-30-90-60, 80' SOCM,  
 120' SOCMW, BHP 1166-1142#, FP 23-  
 110#  
 DST (2) 3890-3925/30-30-30-30, 140'  
 OCM, BHP 1166-871#, FP 23-86#  
 DST (3) 3922-52/30-30-90-60, 480' GIP,  
 150' CO, 120HO&GCM, 150' VHO&GCM,  
 BHP 1182-1182#, FP 31-173#  
 DST (4) 3984-4020/30-30-90-60, 1010'  
 SW, W/SP O, BHP 544-712#, FP 120-  
 488#  
 DST (5) 4058-4150/30-30-30-30, 5'M,  
 BHP 144-112#, FP 88-88#  
 DST (6) 4190-4250/30-30-30-30, 15'M,  
 W/SP O, BHP 104-88#, FP 64-64#

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

15811