

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21460-00-01
Spot: W2W2SW Sec/Twnshp/Rge: 2-23S-17W
1320 feet from S Section Line, 400 feet from W Section Line
Lease/Unit Name: B & W SALES Well Number: 1-2
County: PAWNEE Total Vertical Depth: 4350 feet

Operator License No.: 32891
Op Name: HIMCO OIL & GAS, INC.
Address: PO BOX 2365 UNIVERSITY STATION
ENID, OK 73702

Production Casing Size: 5.5 feet: 4347 WITH 325 SX CMT
Surface Casing Size: 8.625 feet: 365 WITH 225 SX CMT

141 38

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/05/2004 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3790' & 5 SX CMT. PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2004 11:43 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4295'. PERFS AT 3891-95, 4164-72, & 4208-13'. SAND TO 3790' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1130' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 20 SX CMT.

RECEIVED
JAN 14 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2317' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JAN - 9 2004
KCC Dodge City

Signed

Richard M. Lacey

(TECHNICIAN)

INVOICED
DATE 1-14-04
WEL NO. 2004061060

Form CP-2/3