

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22142-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 14-22S-12W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: KRANKENBERG Well Number: 1
County: STAFFORD Total Vertical Depth: 3730 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

Production Casing Size: 5.5 feet: 3729 WITH 175 SX CMT
Surface Casing Size: 8.625 feet: 305 WITH 250 SX CMT

#121²³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2003 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3500' & 5 SX CMT. PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2003 10:10 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 3668'. PERFS AT 3598-3604 & 3612-3622'. ANHYDRITE @ 642'. SANDED TO 3500' & PLACED 5 SX CMT ON TOP OF SAND WITH DUMP BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 700 PSIG. INITIAL SHUT IN PRESSURE 425 PSIG.

RECEIVED
JAN 14 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2330' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Yacef

(TECHNICIAN)

INVOICED

DATE

1-14-04

INV. NO.

2004061061