

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22464-00-00
Spot: NESWNW Sec/Twnshp/Rge: 18-22S-11W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: IVY Well Number: 1
County: STAFFORD Total Vertical Depth: 3645 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

Production Casing Size: 5.5 feet: 3636 WITH 125 SX CMT
Surface Casing Size: 8.625 feet: 344 WITH 250 SX CMT

#118⁴⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2003 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3420' & 5 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 370' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2003 2:55 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 3620'. PERFS AT 3540-3550'. ANHYDRITE @ 580-600'. SANDED TO 3420' & PLACED 5 SX CMT ON TOP OF SAND WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 370' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED
JAN 14 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2020' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed _____

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 1-14-04
INV. NO. 2004061061

FORM CP-275