

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21189-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 18-21S-15W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: TURNER Well Number: 1-C  
County: PAWNEE Total Vertical Depth: 3875 feet

Operator License No.: 30517  
Op Name: TURNCO DRILLING, INC.  
Address: PO BOX 460  
GREAT BEND, KS 67530

Production Casing Size: 4.5 feet: 3874 WITH 175 SX CMT  
Surface Casing Size: 8.625 feet: 960 WITH 450 SX CMT

#124<sup>94</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/08/2004 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SANDED TO 3660' & 4 SX CMT. PLUG AT 1000' WITH 100# HULL - 10 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/08/2004 9:49 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3798-3800'. SANDED TO 3660' & 4 SX CMT ON TOP OF SAND WITH BAILER. 1ST PLUG AT 1000' WITH 100# HULLS - 10 SX GEL - 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
JAN 14 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2140' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
JAN - 9 2004  
KCC Dodge City

Signed

Richard M. Lacey

(TECHNICIAN)

INVOICED

DATE 1-14-04  
INV. NO. 2004061064

[Signature]  
KCC WP-2/3