

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record

K.A.R. -82-3-117  
**RECEIVED**

API NUMBER 15-077-21468-0000  
LEASE NAME Mathes  
WELL NUMBER 1-A

TYPE OR PRINT

NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

JAN 12 2004

KCC WICHITA

265 Ft. from North Line of Section  
350 Ft. from East Line of Section

LEASE OPERATOR Becker Oil Corporation SPOT LOCATION Ne Nw Ne  
ADDRESS 122 E. Grand St., Ste. 212 Section 29 Township 31s Range 7w  
CITY, STATE, ZIP Ponca City, Oklahoma 74660 #31093 County Harper  
PHONE # 303-816-2013 Date Well Completed 12/30/03  
Character of Well Dry and Abandoned Date Plugging Commenced 12/30/03  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 12/30/03

The plugging proposal was approved on 12/29/03 (date)  
by Doug Lewis (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 2240

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	30			
Redbeds	Shale	30	245	8.5/8"	228'	0'
<i>Surf</i>			239	8.625	239'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Received plugging orders from Doug Lewis on 12/29/03. Plugged using 160 sx 60/40 Poz; 4% Gel.

Heavy mud in hole and between all plugs. Bottom plug @ 1500'/35sx; 2nd plug @ 1000'/35sx;

3rd plug @ 290'/50sx; top plug @ 60'/25 sx cemented to surface. Plugged rathole 15 sx, no mousehole.

Plugging completed at 7:00 am 12/30/03 by Allied Cementing, ticket # 15028. Reported to KCC 12/30/03.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Becker Oil Corporation (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.


Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*  
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 9th day of January, 19 2004

*Pamela S. Fields*  
(Notary Public)



My Commission Expires:

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

## Mathes 1-A

**LOCATION:** Ne Nw Ne  
**API:** 15-077-21468-0000

Section 29 T 31s R 7w  
Harper County, Kansas

**OWNER:** Becker Oil Corporation  
**CONTRACTOR:** Sterling Drilling Company, Rig #4

**COMMENCED:** 22-Dec-03  
**COMPLETED:** 30-Dec-03

**TOTAL DEPTH:** **DRILLER**

2240
------

**FEET**  
**LOGGER**

No Log
--------

**FEET**

**Ground Elevation:** 1501  
**KB Elevation:** 1510

### LOG

0 -	2 FEET	Top Soil
2 -	205 FEET	Clay
205 -	880 FEET	Redbeds
880 -	1380 FEET	Shales and Salt
1380 -	2240 FEET	Limestone, Shale and Dolomite

### CASING RECORDS

#### Surface Casing-8-5/8"

Spud at 10:00 am on 12/22/03. Drilled 12-1/4" hole to 245'. Ran 5 joints new, 23# 8-5/8" surface casing. Tally 228' set at 239' KB. Cemented with 200 sx 60/40 Poz; 3% CC. 2% Gel, 1% Ammonia. Cement did circulate. Plug down at 4:45 pm on 12/22/03. By Allied Cementing. Ticket # 14603. Strapped bottom 3 joints, welded collars on remaining 2 joints of surface casing.

#### Production Casing

Received plugging orders from Doug Lewis on 12/29/03. Plugged using 160 sx 60/40 Poz; 4% Gel. Heavy mud in hole and between all plugs. Bottom plug @ 1500'/35sx; 2nd plug @ 1000'/35sx; 3rd plug @ 290'/50sx; top plug @ 60'/25 sx cemented to surface. Plugged rathole 15 sx, no mousehole. Plugging completed at 7:00 am 12/30/03 by Allied Cementing, ticket # 15028. Reported to KCC 12/30/03.

### DEVIATION SURVEYS

3/4	degree(s) at	245	feet
1/2	degree(s) at	780	feet
0	degree(s) at	1540	feet
1	degree(s) at	2240	feet