

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

JAN 08 2004

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: DaMar Resources, Inc.

Address: P. O. Box 70

Phone: (785) 625-0020 Operator License #: 9067

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/2003 11-24-03 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Fort Scott Depth to Top: 4232 Bottom: 4255 T.D.

Miss. Warsaw Depth to Top: 4318 Bottom: T.D. 4348

Depth to Top: Bottom: T.D.

API Number: 15 - 135-20,116 - 00 00

Lease Name: Betz 'B'

Well Number: 1

Spot Location (QQQQ): C - C - NW - NE 660 Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 13 Twp. 20 S. R. 23 East West

County: Ness

Date Well Completed: 2/23/1968

Plugging Commenced: 12/16/2003

Plugging Completed: 12/16/2003

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes handwritten entries for Anhydrite and Prod.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Pump 25 sx of 60-40 pozmix cement with 6% gel and 250# of hulls down 2 3/8" tubing, displace with 9 bbl of water, pressure up to 300#. Pump 20 sx of 60-40 pozmix cement down 8 5/8 - 4 1/2 annulus, pressure to 500#. Perforate 3 holes @ 720'. Pump 85 sx 60-40 pozmix cement with 6% gel down 2 3/8" tubing, circulated to surface between 2 7/8" and 4 1/2" annulus with 20 sx out, shut in annulus, put away rest of cement up to 600#.

Name of Plugging Contractor: DaMar Resources, Inc. Swift Services Inc License #: 0007 32382

Address: P. O. Box 70 Hays, KS 67601

Name of Party Responsible for Plugging Fees: DaMar Resources, Inc.


State of Kansas County, Ellis, ss.

Curtis R. Longpine (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address) P. O. Box 70 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 6 day of January, 20 04

Vickie Cole My Commission Expires: 10-18-04 Notary Public