

RECEIVED

DEC 31 2003

KCC WICHITA

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

LEASE NAME Heroneme

WELL NUMBER 1

1090 Ft. from 8(N) Line of Section (circle one)

2310 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR White Eagle Resources

ADDRESS P.O. Box 187

CITY, STATE, ZIP Plainville Ks 67663

PHONE#(785) 737-3726 OPERATORS LICENSE NO. 31430

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION - SW - NW - NE

SEC. 17 TWP. 9 S. RGE 19 (N) or (W)

COUNTY Rooks

Date Well Completed 12-17-1968

Date Plugging Commenced 11-20-03

Date Plugging Completed 11-20-03

The plugging proposal was approved on 11/14/03 1-6-04 (date)

by Rich Williams (KCC District Agent's Name)

Is ACO-1 filed? NO If not, is well log attached? NO

Producing Formation(s) Toronto LKC DTS A-Buckle Depth to Top 3266 Bottom 3556 T.D. 3688

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
<u>Surf</u>	<u>10 3/4 casing</u>	<u>0</u>	<u>242</u>	<u>10 3/4</u>	<u>- 242</u>	<u>⊗</u>
	<u>7" casing</u>	<u>0</u>	<u>3588</u>	<u>7"</u>	<u>- 3588</u>	<u>⊗</u>

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 0 feet to 3548 feet each set.

Pumped 50 sacks 60/40 pps w/ 10% gel and 200# hulls followed w/ 11 sacks of gel.

Then pumped 330 sacks cement.

Max P.S.I. 500# S.I.P. 400#

Hooked up to annulus. Instant pressure at 520#
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing

License No. _____

Address 24 S. Lincoln Street Russell Ks

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: White Eagle Resources

STATE OF Colorado COUNTY OF Boulder, ss.

Randy Weigel (Employee of Operator or (Operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Randy Weigel

(Address) 2190 16 Rd Plainville, Ks

SUBSCRIBED AND SWORN TO before me this 18th day of December, 192003

S. J. Stahl
Notary

My Commission Expires: 03-05-06

