

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED  
JAN 14 2004  
KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Gore Oil Company  
Address: P.O. Box 2757, Wichita, KS 67201-2757  
Phone: (316) 263-3535 Operator License #: 5552  
Type of Well: oil Docket #: n/a  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 9-29-03 (Date)  
by: David P. Williams (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Kansas City Depth to Top: 3901' Bottom: 4240' T.D. 4240'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 153-20719 - 00 - 00  
Lease Name: Vap  
Well Number: 3  
Spot Location (QQQQ): N/2 - NE - SE - SE  
1155 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 20 Twp. 1 S. R. 33  East  West  
County: Rawlins  
Date Well Completed: 7-21-88  
Plugging Commenced: 11-13-03  
Plugging Completed: 11-13-03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	303'	8 5/8"	303'	0'
		0	4236'	4 1/2"	4236'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Open end tubing at 4000'. Pump 75 sx SMD cement w/200# hulls. Pull tubing to 2000'. Pump 65 sx SMD cement w/300# hulls. Cement circ to surface. Pull tbg OOH. Hook up to 4 1/2" & pump 25 sx cmt @ 75# max. Hook up to 8 5/8" & pump 25 sx cmt @ 300# max. Shut in 8 5/8" @ 175#. Wait 1 hr. Pump 10 sx down 4 1/2". Top off 4 1/2" & 8 5/8" w/20 sx cmt. Job complete.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382  
Address: P.O. Box 466, Ness City, KS 67560-0466

Name of Party Responsible for Plugging Fees: Gore Oil Company  
State of Kansas County, Sedgwick, ss.

Larry M. Jack (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Larry M. Jack  
(Address) Wichita, KS



SUBSCRIBED and SWORN TO before me this 9th day of January, 20 04  
Rebecca K. Crawford My Commission Expires: 3-20-07  
Notary Public