

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD

Form CP-4  
September 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

RECEIVED

DEC 03 2003

KCC WICHITA

Lease Operator: JERRY PATTERSON OIL

Address: PO BOX 307

Phone: (785) 689-4897 Operator License #: 9559

Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 11/10/03 (Date)

by: DENNIS HAMEL (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

LKC Depth to Top: 3223 Bottom: 3230 T.D. \_\_\_\_\_

LKC Depth to Top: 3238 Bottom: 3246 T.D. 3396

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-147-30014-00-02

Lease Name: WALLGREN

Well Number: 1

Spot Location (QQQQ): E-1/2 - N 1/2 - SE

1980 Feet from  North /  South Section Line

660 Feet from  East /  West Section Line

Sec. 34 Twp. 4 S. R. 20  East  West

County: PHILLIPS

Date Well Completed: 11/07/64

Plugging Commenced: 11/10/03

Plugging Completed: 11/10/03

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	<del>230</del> 224	8 5/8	230 224	NONE
		0	3395	4 1/2	3395	NONE
		0	3318	2 3/8	3318	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

HOOKEED UP TO TBG. AND PUMPED 70 SACKS SMD CEMENT WITH 200# CS HULLS MAX PRESSURE @1800 #

HOOKEED UP TO ANNULAS BETWEEN 2 3/8 AND 4 1/2 AND PUMPED 5/10 BBL. CEMENT (TBG. HAD BEEN PREVIOUSLY CEMENTED IN THE HOLE) PRESSURED TO 600# HOOK UP TO 8 5/8 AND PUMPED 30 SKS. SMD CEMENT & 100 # HULLS MAX PRESSURE 700# TBG, CASEING, AND SURFACE PIPE ALL STANDING FULL OF CEMENT.

Name of Plugging Contractor: SWIFT SERVICES License #: 32382

Address: PO BOX 466 NESS CITY KANSAS 67560

Name of Party Responsible for Plugging Fees: JERRY PATTERSON OIL

State of KANSAS County, PHILLIPS, ss.

JERRY PATTERSON (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jerry Patterson

(Address) BOX 307 NESS, KS. 67646

SUBSCRIBED and SWORN TO before me this 2nd day of December, 2003

Laura L. Zillinger My Commission Expires: 4-24-04  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 Bm