

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-065-20249-00-01

LEASE NAME SE GANO UNIT Wichita,

TYPE OR PRINT

WELL NUMBER 2-1 INJ

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

1650 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR Murfin Drilling Co., Inc.

SEC 12 TWP. 10S RGE. 24W (E) or (W)

ADDRESS 250 N. Water, Suite 300, Wichita, KS 67202

COUNTY GRAHAM

PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606

Date Well Completed 8/9/69

Character of Well INJ (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging commenced 11/4/03

Plugging Completed 11/4/03

The plugging proposal was approved on 11/4/03

(date)

by Rich Williams w/KCC Hays, KS.

(KCC District Agent's Name).

Is ACO-1 filed? ?

If not, is well log attached? no

Producing Formation _____ Depth to Top 3778 Bottom 4008' TD 4080 Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	181 181	8 5/8	181 181	0
		Production	4079	4 1/2"	4079	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Ran tbg to 2516'. Pumped 75 sxs SMD & 300#hulls. Pulled tbg to 643'. Pumped 55 sxs SMD & 200 # hulls. Circ cmt to sur. Tied onto 8 5/8". Pumped 12 sxs SMD & circ cmt out of 4 1/2". SI 8 5/8. Tied onto 4 1/2 csg. Pumped 18 sxs. Pressured to 400#. ISIP 200#.

Witnessed by Rich Williams w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606 Address 250 N. Water, Suite 300, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) *Tom W. Nichols*

(Address) Wichita, KS

SUBSCRIBED AND SWORN TO before me this 10th day of November 2003

Notary Public - Barbara J. Dodson *Barbara J. Dodson*

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



RECEIVED
DEC 08 2003
KCC WICHITA

SWIFT SERVICES, INC.

PO BOX 466

NESS CITY, 67560-0466

Invoice

DATE	INVOICE #
11/4/03	5816

BILL TO
Murfin Drilling Co Inc PO Box 130 Hill City, KS 67642

PA
APPROVED

RECEIVED
DEC 08 2003
KCC WICHITA
DEC 1 2003

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Operator	Job Purpose
Net 30	2-1	Gano	Graham		Oil	Abandoned	Lenny	PTA
PRICE REFERE...	DESCRIPTION				QTY	UNIT PRICE	AMOUNT	
575W	Milage				50	2.50	125.00T	
576W-P	Pump Charge				1	550.00	550.00T	
330	Swift Multi-Density				160	9.75	1,560.00T	
275	Cotton Seed Hulls				7	20.00	140.00T	
581W	Service Charge Cement				200	1.00	200.00T	
583W	Drayage				498	0.85	423.30T	
	Subtotal						2,998.30	
	Sales Tax						5.30%	158.91
Thank you for your business.							Total	\$3,157.21



CHARGE TO: *Murfin Dely Co.*
 ADDRESS:
 CITY, STATE, ZIP CODE: *Hill City, Ks*

RECEIVED
 DEC 08 2003
 KCC WICHITA

TICKET No 5816

PAGE 1 OF 1

SERVICE LOCATIONS 1. <i>Hoys K</i>	WELL/PROJECT NO. <i>2-1</i>	LEASE <i>Garo</i>	COUNTY/PARISH <i>Graham</i>	STATE <i>Ks</i>	CITY	DATE <i>11-4-03</i>	OWNER <i>Same</i>
2.	TICKET TYPE <input checked="" type="checkbox"/> SERVICE <input type="checkbox"/> SALES	CONTRACTOR	RIG NAME/NO. <i>Murfin</i>	SHIPPED VIA <i>105</i>	DELIVERED TO <i>S.W. Hill City</i>	ORDER NO.	
3.	WELL TYPE <i>oil</i>	WELL CATEGORY <i>Abandoned</i>	JOB PURPOSE <i>PTA</i>	WELL PERMIT NO.	WELL LOCATION		
4.	REFERRAL LOCATION	INVOICE INSTRUCTIONS					

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	ACCOUNTING			DESCRIPTION	QTY.		U/M		UNIT PRICE	AMOUNT	
		LOC	ACCT	DF								
<i>575</i>					<i>MILEAGE 105</i>	<i>50</i>	<i>mi</i>			<i>2.50</i>	<i>125</i>	<i>00</i>
<i>576</i>					<i>Pump change</i>	<i>1</i>	<i>EA</i>				<i>550</i>	<i>00</i>
<i>330</i>					<i>5m O Cement</i>	<i>160</i>	<i>SKS</i>			<i>9.75</i>	<i>1560</i>	<i>00</i>
<i>275</i>					<i>Hulls</i>	<i>7</i>	<i>SKS</i>			<i>20.00</i>	<i>140</i>	<i>00</i>
<i>581</i>					<i>Bulk service change</i>	<i>200</i>					<i>200</i>	<i>00</i>
<i>583</i>					<i>Drayage</i>	<i>498</i>		<i>7.M</i>		<i>85</i>	<i>423</i>	<i>30</i>

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, **PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY** provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

X
 DATE SIGNED *11-4-03* TIME SIGNED *9:00* A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY	AGREE	UN-DECIDED	DIS-AGREE	PAGE TOTAL	<i>2998</i>	<i>30</i>
OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?						
WE UNDERSTOOD AND MET YOUR NEEDS?						
OUR SERVICE WAS PERFORMED WITHOUT DELAY?						
WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?				TAX	<i>158</i>	<i>91</i>
ARE YOU SATISFIED WITH OUR SERVICE? <input type="checkbox"/> YES <input type="checkbox"/> NO				TOTAL	<i>3157</i>	<i>121</i>
<input type="checkbox"/> CUSTOMER DID NOT WISH TO RESPOND						

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR: *Remy* APPROVAL: *John Lovestrom*

Thank You!

JOB LOG

SWIFT Services, Inc.

DATE 11-4-03 PAGE NO. 7

CUSTOMER *Murphy Dry Co.* WELL NO. *2-1* LEASE *Gano* JOB TYPE *PTA* TICKET NO. *5816*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0830							on loc open End Tbg at 2516 W.L.T.D. 3876 Bottom Perf 4008 4 1/2 CSC
75	0915	4	40 BBL					Pump 75 SKS 5MD Cement w/ 300 # Hulls no circ to Pit
55	0930							Pull Tbg To 1000 643' Pump 55 SKS 5MD CMT w/ 200 # Hulls CMT Circ to Pit
12	1036							Pull Tbg out of Lolo hook up to 8 5/8 + Pump 12 SKS CMT Circ out 4 1/2 close 8 5/8
18								hook up to 4 1/2 + Pump 18 SKS CMT Down 4 1/2 max PSI 400 Shut in 4 1/2 200
	1115							Job Complete
								160 SKS CMT Total 500 # hulls

RECEIVED

DEC 08 2003

KCC WICHITA