

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-25560-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 3-30S-17E
314 feet from S Section Line, 2166 feet from E Section Line
Lease/Unit Name: STEVE ERBE Well Number: 2
County: WILSON Total Vertical Depth: 470 feet

Operator License No.: 31796
Op Name: QUEST ENERGY SERVICE INC.
Address: PO BOX 100
BENEDICT, KS 66714

Surface Casing Size: 8.625 feet: 24

#35

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 09/22/2003 8:00 AM
Plug Co. License No.: 9313 Plug Co. Name: LORENZ, JAMES D.
Proposal Rcvd. from: DICK CORNELL Company: QUEST ENERGY SERVICE, INC. Phone: (620) 698-2250

Proposed
Plugging
Method:

CLEAN WELL OUT TO BOTTOM AND CIRCULATE PORTLAND CEMENT TO SURFACE.

Plugging Proposal Received By: JOHN ALMOND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/22/2003 5:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

WHEN DRILLER HIT LANSING-KANSAS CITY LIME, THE WELL STARTED FLOWING WATER, AS THEY CONTINUED TO DRILL, THEY LOST CIRCULATION. THEY TRIED TO PLUG WELL AT 470' AND PUMPED 225 SACKS OF PORTLAND CEMENT AND 12 SACKS OF COTTONSEED HULLS AND DID NOT REGAIN CIRCULATION. THEY WAITED UNTIL THE NEXT DAY AND STILL COULD NOT GET CIRCULATION. THEY PUSHED A RUBBER PLUG DOWN TO 285' AND CIRCULATED PORTLAND CEMENT TO SURFACE. PLUGGED WELL WITH 90 ADDITIONAL SACKS OF PORTLAND CEMENT.

RECEIVED
KCC at #3

RECEIVED
JAN 15 2004
KCC WICHITA

JAN 13 2004

BL

Charlotte NC

Remarks: CORRECTED TO GPS FOOTAGES

Plugged through:

District: 03

Signed

John Almond by BL
(TECHNICIAN)

INVOICED
DATE 1-16-04
2004061068