

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22963-00-00  
Spot: S2NWNW Sec/Twnshp/Rge: 4-27S-6E  
925 feet from N Section Line, 650 feet from W Section Line  
Lease/Unit Name: RALSTON Well Number: 2  
County: BUTLER Total Vertical Depth: 2805 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 125 N. MARKET ST. SUITE 1120  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 2803 75 SX CMT  
Surface Casing Size: 8.625 feet: 220 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/07/2004 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: ALAN NATION Company: RANGE OIL COMPANY, INC. Phone: (316) 250-5163

Proposed Plugging Method: See actual report.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 16 2004  
RECEIVED  
KCC DISTRICT #2  
JAN 14 2004  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/07/2004 12:00 PM KCC Agent: DONALD HOBERECHT

**Actual Plugging Report:**

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Ran 1" tubing inside 4-1/2" casing. Circulated cement to surface with 24-1/2 sacks of 60/40 poz mix with 4% gel.

Pulled 1" tubing and ran tubing down outside 4-1/2" casing to 250'. Circulated cement to surface with 66-1/2 sacks of 60/40 poz mix with 4% gel.

Remarks: UNITED CEMENT TICKET #5075

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

**INVOICED**

DATE

1-16-04

INV. NO.

2004061074