

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-049-20290-00-00  
Spot: SENESE Sec/Twnshp/Rge: 14-31S-10E  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: CHAFFIN Well Number: 25  
County: ELK Total Vertical Depth: 1986 feet

Operator License No.: 3591  
Op Name: TRIBOULET, ED DBA C & E OIL CO.  
Address: RR1, BOX 1B2  
MOLINE, KS 67353

Production Casing Size: 5.5 feet: 1969  
Surface Casing Size: 8.625 feet: 50

*1664<sup>55</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2003 8:00 AM  
Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.  
Proposal Rcvd. from: ED TRIBOULET Company: TRIBOULET, ED DBA C & E OIL C Phone: (316) 647-3601

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM, MIDDLE AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/18/2003 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

DUMP BAILED SAND BACK TO 1855'. RAN 2" TUBING IN 5.5" CASING TO 1855' AND PUMPED 5 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1100' AND PUMPED 4 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" OUT. RIPPED 5.5" AND PULLED 850' OF 5.5" OUT. RAN 2" BACK IN TO 350' AND PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" AND TOPPED OFF WELL. USED TOTAL OF 67 SACKS CEMENT.

RECEIVED KCC District #3  
JAN 15 2004  
KCC WICHITA  
JAN 13 2004  
Chanute, KS

Remarks:

Plugged through:

District: 03

Signed Ron Rowe by RB  
(TECHNICIAN)

INVOICED  
DATE 1-16-04  
TEL NO. 2004061070