

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-20967-00-00
Spot: SESESE Sec/Twnshp/Rge: 2-32S-10E
330 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: ROGERS Well Number: 1
County: CHAUTAUQUA Total Vertical Depth: 2050 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1, BOX 1B2
MOLINE, KS 67353

Production Casing Size: 4.5 feet: 2050

\$ 66⁶³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2003 8:00 AM
Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.
Proposal Rcvd. from: ED TRIBOULET Company: TRIBOULET, ED DBA C & E OIL C Phone: (316) 647-3601

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM, MIDDLE AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE Witness Type: PARTIAL
Date/Time Plugging Completed: 12/05/2003 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

DUMP BAILED SAND BACK TO 1920'. RAN 2" TUBING IN 4.5" CASING TO 1920' AND PUMPED 5 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1050' AND PUMPED 4 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" OUT. RIPPED 4.5" CASING AND PULLED 930' OF 4.5" PIPE. RAN 2" BACK IN TO 350' AND PUMPED/CIRCULATED 58 SACKS CEMENT TO SURFACE. PULLED 2" AND TOPPED OFF WELL. USED TOTAL OF 67 SACKS CEMENT.

RECEIVED
KCC District #3

JAN 13 2004

Chanute, KS

RECEIVED

JAN 15 2004

BL
KCC WICHITA

Remarks:

Plugged through:

District: 03

Signed

Ron Rowe by BL
(TECHNICIAN)

INVOICED
DATE 1-16-04
INV. NO. 2004061070