

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-21770-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 2-32S-10E
4950 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: BARNER-JULIAN Well Number: 4
County: CHAUTAUQUA Total Vertical Depth: 2200 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1, BOX 1B2
MOLINE, KS 67353

Production Casing Size: 4.5 feet: 2200

\$7150

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2003 8:00 AM
Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.
Proposal Rcvd. from: ED TRIBOULET Company: TRIBOULET, ED DBA C & E OIL C Phone: (316) 647-3601

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM, MIDDLE AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 12/03/2003 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

CIBP PREVIOUSLY SET AT 1986'. DUMP BAILED SAND BACK TO 1820'. RAN 2" IN TO 1820' AND PUMPED 5 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1100' AND PUMPED FOR MIDDLE PLUG. PULLED 2" AND RIPPED AND PULLED 1034' OF 4.5" OUT. RAN 2" BACK IN TO 350' AND PUMPED/CIRCULATED 61 SACKS CEMENT. PULLED 2" AND TOPPED OFF WELL. USED TOTAL OF 70 SACKS CEMENT.

RECEIVED
KCC District #3
JAN 13 2004 *BL*
Chanute, KS

RECEIVED
JAN 15 2004
KCC WICHITA

Remarks:

Plugged through:

District: 03

Signed

Ron Rowe by BL

(TECHNICIAN)

INVOICED

DATE 1-16-04

INV. NO. 2004061070