

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-049-20172-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 18-31S-10E  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: WILSON L Well Number: 2  
County: ELK Total Vertical Depth: 2166 feet

Operator License No.: 3591  
Op Name: TRIBOULET, ED DBA C & E OIL CO.  
Address: RR1, BOX 1B2  
MOLINE, KS 67353

Production Casing Size: 5.5 feet: 2164  
Surface Casing Size: 8.625 feet: 106

\$70<sup>40</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2003 8:00 AM  
Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.  
Proposal Rcvd. from: ED TRIBOULET Company: TRIBOULET, ED DBA C & E OIL C Phone: (620) 647-3601

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM, MIDDLE AND TOP PLUGS.

Plugging Proposal Received By: RON ROWE Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/19/2003 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

DUMP BAILED SAND BACK TO 2050'. RAN 2" TUBING IN 5.5" CASING TO 2045' AND PUMPED 5 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1150' AND PUMPED 4 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" OUT. RIPPED 5.5" AND PULLED 700' OF 5.5" OUT. RAN 2" BACK IN TO 425' AND PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" AND TOPPED OFF WELL. USED TOTAL OF 70 SACKS CEMENT.

RECEIVED  
KCC District #3

JAN 13 2004

Chanute, KS

RECEIVED

JAN 15 2004

KCC WICHITA

Remarks:

Plugged through:

District: 03

Signed

Ron Rowe by Bl

(TECHNICIAN)

INVOICED

DATE

1-16-04

INV. NO.

2004061070