

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-20196-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 14-31S-10E
2210 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: CHAFFIN Well Number: 23
County: ELK Total Vertical Depth: 1965 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1, BOX 1B2
MOLINE, KS 67353

Production Casing Size: 5.5 feet: 1962
Surface Casing Size: 8.625 feet: 50

86
#63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2003 8:00 AM
Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.
Proposal Rcvd. from: ED TRIBOULET Company: TRIBOULET, ED DBA C & E OIL C Phone: (316) 647-3601

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM, MIDDLE AND TOP PLUGS

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 12/17/2003 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

DUMP BAILED SAND BACK TO 1850'. RAN 2" TUBING IN 5.5" CASING TO 1850' AND PUMPED 5 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1100' AND PUMPED 4 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" OUT. RIPPED 5.5" AND PULLED 1000' OF 5.5" OUT. RAN 2" BACK IN TO 350' AND PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" AND TOPPED OFF WELL. USED TOTAL OF 70 SACKS CEMENT.

RECEIVED
KCC District #3

RECEIVED
JAN 13 2004
JAN 15 2004
KCC WICHITA
Charute, KS

Remarks:

Plugged through:

District: 03

Signed

Ron Rowe by BL
(TECHNICIAN)

INVOICED
DATE 1-16-04
INV. NOS. 2004061070