

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-20198-00-00
Spot: SENWSE Sec/Twnshp/Rge: 14-31S-10E
1450 feet from S Section Line, 1490 feet from E Section Line
Lease/Unit Name: CHAFFIN Well Number: 24
County: ELK Total Vertical Depth: 1964 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1, BOX 1B2
MOLINE, KS 67353

Production Casing Size: 5.5 feet: 1964
Surface Casing Size: 8.625 feet: 50 *463⁸³*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2003 8:00 AM
Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.
Proposal Rcvd. from: ED TRIBOULET Company: TRIBOULET, ED DBA C & E OIL C Phone: (316) 647-3601

Proposed Plugging Method: TO PUMP CEMENT FOR BOTTOM, MIDDLE AND TOP PLUGS

Plugging Proposal Received By: RON ROWE Witness Type: PARTIAL
Date/Time Plugging Completed: 12/17/2003 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

DUMP BAILED SAND BACK TO 1860'. RAN 2" TUBING IN 5.5" CASING TO 1860' AND PUMPED 5 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1000' AND PUMPED 4 SACKS CEMENT FOR MIDDLE PLUG. PULLED 2" OUT. RIPPED 5.5" AND PULLED 800' OF 5.5" OUT. RAN 2" BACK IN TO 350' AND PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" AND TOPPED OFF WELL. USED TOTAL OF 70 SACKS CEMENT.

RECEIVED
KCC District #3
RECEIVED
JAN 15 2004
KCC WICHITA Chanute, KS
JAN 13 2004 *SL*

Remarks:

Plugged through:

District: 03

Signed Ron Rowe by SL
(TECHNICIAN)

INVOICED
DATE 1-16-04
NO. 2004061970