

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22857-00-00
Spot: NWNENW Sec/Twnshp/Rge: 33-13S-14W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: BOXBERGER Well Number: 7
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 7281
Op Name: VONFELDT, ALAN J
Address: 128 EVES DRIVE
RUSSELL, KS 67665

Production Casing Size: 5.5 feet: 3348 150 COMMON
Surface Casing Size: 8.625 feet: 228 140 60/40 POZ

#10888

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2003 12:00 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: ALAN VONFELDT Company: VONFELDT, ALAN J. Phone: (785) 483-6446

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2003 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto casing and pumped 250 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 800#. Pressured backside to Max. P.S.I. 500#.

RECEIVED
JAN 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 1-20-04
INV. NO. 2004061080

JAN 09 2004

VONFELDT OIL OPERATIONS, INC
RUSSELL, KS 67665

33-13 -14W
NW NE NW

#7 BOXBERGER

site: 3/4 W OF RUSSELL, KS
contr: VONFELDT DRILLING
geol: DAVID SHUMAKER

city: RUSSELL
field: RUSSELL

API 15-167-22857

fr date 08/02/89 spd date 08/07/89 drig comp 08/13/89 card issued 09/13/89 last revised 09/13/89

ELV: 1867 KB LOG
tops.....depth/datum
ANH.....899 +968
B/ANH.....934 +933
TOP.....2740 -873
HEEB.....2967 -1100
TOR.....2986 -1119
DOUG.....2998 -1131
LANS.....3022 -1155
BKC.....3269 -1402
ARB WEA.....3281 -1414
ARB.....3289 -1422
LTD.....3349 -1482
RTD.....3350 -1483

IP status:

OIL, P 15 BO & 150 BWPD, ARB 3293-3295,
CSG: 8-5/8" 228 / 140 SX, 5-1/2" 3348 / 150 SX
NO CORES
DST (1) 3271-3297 (ARB), / 30-30-30-30, (1ST OP) SB,
(2ND OP) SB, REC 1800' OCW ISIP 1040# FSIP 1032#
IFP 100# -326# FFP 367# -551# IHP 1832# FHP 1816#
MICT - CO, PF (ARB) 3293-3295, W / 2 SPF, GSO, NAT,
SET 2-1/2" TBG AT 3290, NO PKR, POP, P 15 BO & 150
BWPD (GR 36), 9/4/89

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

5301025