

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03399-00-00

Spot: SWNENE

Sec/Twnshp/Rge: 25-16S-12W

4290 feet from S Section Line,

990 feet from E Section Line

Lease/Unit Name: RIEMANN

Well Number: 1

County: BARTON

Total Vertical Depth: 3344 feet

Operator License No.: 6883

Op Name: ROBINOWITZ OIL COMPANY

Address: 7130 S. LEWIS, STE 910
TULSA, OK 74136

Production Casing Size: 5.5 feet: 3331 40 SX CMT

Surface Casing Size: 10.75 feet: 777

108⁶⁸

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/12/2004 3:00 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-2299

Proposed Plugging Method: Ordered 480 sxs 60/40 pozmix - 10% gel - 600# hulls.
Open hole 3334' - 3344'.
Log Tech perfed at 775' - 1475' - two shot perf.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 01/12/2004 6:00 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing RIH with tubing to 1500'.
Allied Cementing tied onto tubing and pumped 190 sxs 60/40 pozmix with 500# hulls mixed in to circulate cement to surface.
Pulled tubing and tied onto 5 1/2" casing with a swedge.
Pumped an additional 220 sxs cement with 100# hulls mixed in to circulate cement out backside.
Shut in backside and pumped 70 sxs 60/40 pozmix.
Max. P.S.I. 400#. S.I.P. 200#.

RECEIVED

JAN 16 2004

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #14341.

Plugged through: TBG

District: 04

Signed

Pat Staab

(TECHNICIAN)

INVOICED

DATE 1-20-04
REV. NO. 2004061079

Form CP-2/3

JAN 14 2004

BLACK MARSHALL

#7 RIEMAN

25-16-12W
SW NE NE

Contr.

BARTON

County

E 1930

Comm.

7-31-46

Comp.

3-10-46

IP

17 BOPD & 17 BW

Tops	Depth	Datum
ANHY.	775	
B'SD	3334	
TD	3344	

Casing

12" 481

5" 3331

10³/₄ 777'

SO 1 GOPH 3025-35

GSO 3325-30; NS

SP & SS to 3344

PAY 3339-44; FU 500' OIH/lhr
tr wlr;INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

INVOICES