

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03394-00-00

Spot: NESENE

Sec/Twnshp/Rge: 25-16S-12W

3630 feet from S Section Line,

330 feet from E Section Line

Lease/Unit Name: RIEMANN

Well Number: 2

County: BARTON

Total Vertical Depth: 3350 feet

Operator License No.: 6883

Op Name: ROBINOWITZ OIL COMPANY

Address: 7130 S. LEWIS, STE 910
TULSA, OK 74136

Production Casing Size: 5.5 feet: 3326 125 SX CMT
Surface Casing Size: 10.75 feet: 773

108

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/13/2004 9:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-2299

Proposed Plugging Method: Ordered 430 sxs 60/40 pozmix - 10% gel - 600# hulls.
Squeeze 5 1/2" w/50 sxs at 1555' - 1585'.
Open hole 3323' - 3350'. Log Tech perfed at 775' - 1475'.
Fluid level 33 seconds to surface.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/13/2004 11:00 AM

KCC Agent: PAT STAAB

Actual Plugging Report:

Allied tied onto 5 1/2" casing with a swedge.
Pumped 400 sxs 60/40 pozmix with 10% gel and 600# hulls mixed in to circulate cement out of backside of 10 3/4" casing to surface.
Shut in backside and pumped 30 sxs cement.
Max. P.S.I. 550#. S.I.P. 450#.

RECEIVED
JAN 16 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET 14342.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

INVOICED

DATE

1-20-04

REV. NO.

2004061079

JAN 14 2004

BLACK MARSHALL OIL CO

#2

RIEMANN

25-16-12W

NE SE NE

Contr.

BARTON

County

E 1933

Comm

7-29-42

Comp

9-11-42

IP

44.9 BOFD

Tops	Depth	Datum
ANHY	768	
TOP	2720	2745
LENS	3095	
CONG	3325	
E SD	3328	
TD	3350	

Casing


12" 470

5" 3326

10³/₄ to 773'

SO 3191-94

PAY 3323-50



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
OCT 1 1942