

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03393-00-00  
Spot: NENENE Sec/Twnshp/Rge: 25-16S-12W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: RIEMANN Well Number: 1  
County: BARTON Total Vertical Depth: 3387 feet

Operator License No.: 6883  
Op Name: ROBINOWITZ OIL COMPANY  
Address: 7130 S. LEWIS, STE 910  
TULSA, OK 74136

Production Casing Size: 5.5 feet: 3362 50 SX CMT  
Surface Casing Size: 10.75 feet: 779

# 110 08

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2004 11:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-2299

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Perfs 3266'. Log Tech perfed 775' - 1475'.  
Dakota 184' - 430'. Anhy. 778' - 798'. Salt 1218' - 1455'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/13/2004 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing RIH with tubing to 1500'.  
Allied Cementing tied onto tubing and pumped 135 sxs 60/40 pozmix with 400# hulls mixed in to circulate cement to surface.  
Pulled tubing and tied onto casing with a swedge.  
Pumped 115 sxs cement with 200# hulls mixed in.  
Max. P.S.I. 700#. S.I.P. 500#.  
Tied onto backside and pumped 50 sxs cement.  
Max. P.S.I. 500#. S.I.P. 300#.

RECEIVED  
JAN 16 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #14343.

Plugged through: TBG

District: 04

Signed Pat Staab  
(TECHNICIAN)

INVOICED

DATE 1-20-04  
INV. NO. 2004061079

JAN 14 2004

BLACK MARSHALL OIL CO

#1

RIEMANN

25-16-12W  
NE NE NE

Contr.

BARTON

County

E 1930

Comm. 5-27-12

Comp. 7-11-12


IP 525 BOPD

Tops	Depth	Datum
ANHY	764	or 778
TOP	2730	
LANE	3088	or 3095
COMG	3351	
ARB	3362	
TD	3387	

Casing

12" 479 10 3/4 to 777  
5" 3362 w 50 5 x 5

SO 3025-35, 3305-11  
Perf 40/3003-11  
A/1000, wtr  
Pulled 5" csg



INDEPENDENT OIL & GAS SERVICE

MAOICEN