

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-23162-00-00  
Spot: NENENW Sec/Twnshp/Rge: 15-7S-19W  
4950 feet from S Section Line, 2970 feet from E Section Line  
Lease/Unit Name: BURTON Well Number: 4  
County: ROOKS Total Vertical Depth: 3455 feet

Operator License No.: 5140  
Op Name: ANGLE, GEORGE A DBA FRONTIER OI  
Address: 1720 KANSAS STATE BANK BLDG.  
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 3448 160 & 350 SX CMT  
Surface Casing Size: 8.625 feet: 264 160 SX CMT  
\$112.<sup>29</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/13/2004 9:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: RICHARD D PARKER Company: FRONTIER OIL COMPANY Phone: (316) 263-1201

Proposed Plugging Method: Ordered 250 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/13/2004 12:30 PM KCC Agent: ROGER MOSES

**Actual Plugging Report:**  
8 5/8" S.P. at 264' w/160 sxs cement. 4 1/2" casing at 3448' w/160 sxs cement.  
Perf 4 1/2" casing at 1490' and circulated with 410 sxs cement.  
RIH with tubing to 2996' - spotted 80 sxs cement with 300# hulls.  
Pulled tubing to 1500' - circulated with 80 sxs cement and 200# hulls.  
Pulled all tubing and topped off 4 1/2" casing with 15 sxs cement.  
Visual inspection of annulus - head full of cement.  
Total of 175 sxs 60/40 pozmix - 10% gel and 500# hulls.

**RECEIVED**  
**JAN 16 2004**  
**KCC WICHITA**

Remarks: ALLIED CEMENTING COMPANY. FONTIER OIL-WATER.

Plugged through: TBG

District: 04

Signed Ray L Moses  
(TECHNICIAN)

**INVOICED**

DATE 1-20-04  
INV. NO. 2004061076

**JAN 15 2004**

STATE: KANSAS COUNTY: ROOKS REISSUE 15-7S-19W  
 FIELD: GROVER NORTH 1/4 MI S PROD (MULTIPAY) NE NE NW  
 OPER: FRONTIER OIL 4950 FSL 2970 FEL SEC  
 WELL: 4 BURTON WELL CLASS: WOE ELEV: 1974 KB  
 API: 15-163-23162 STATUS: OIL 1969 GR  
 SPUD: 04/09/91 COMP: 05/09/91  
 DTD: 3455 LTD: FTD: MARMATON PBTB: 3421

LOC: 4 MI N-NW WEBSTER, KS

IP: COMP 5/9/91, IPP 10 BOPD, 15 BWPD, GTY 35 PROD ZONE- LANSING-KC  
 3150-3366 GROSS  
 NO CORES, ONE DST (LANSING-KC EXTENSION)

SPL TOPS:

|           |            |                     |            |
|-----------|------------|---------------------|------------|
| ANHYDRITE | 1478 496   | LANSING-KANSAS CITY | 3164 -1190 |
| TOPEKA    | 2922 -948  | B/ KANSAS CITY      | 3385 -1411 |
| HEEBNER   | 3122 -1148 | MARMATON            | 3425 -1451 |
| TORONTO   | 3147 -1173 |                     |            |
| TD        | 3455 -1481 |                     |            |

LOG TOPS/TYPES NOT RPTD  
 CSGS: 8 5/8 @ 264 W/160 SX, 4 1/2 @ 3448 W/160 SX, PERF FOR SQZ 1490-1491 W/410  
 SX; TBG: 2 3/8 @ 3415; DRLG COMP 04/16/91 RIG REL 04/16/91

STATE: KANSAS COUNTY: ROOKS REISSUE 15-7S-19W  
 FIELD: GROVER NORTH 1/4 MI S PROD (MULTIPAY) NE NE NW  
 OPER: FRONTIER OIL 4950 FSL 2970 FEL SEC  
 WELL: 4 BURTON WELL CLASS: WOE  
 (CONTINUED)

DSTS: DST # 1 (LANSING-KANSAS CITY) 3300-3370, OP 1 HR, SI 30 MIN, OP 30 MIN, SI  
 30 MIN, REC: 5 FT SOCGM, 120 FT OCGM, IFP 111, FFP 112, IFP 144, FFP 155, ISIP  
 643, FSIP 643;

PERFS: PERF (LANSING-KANSAS CITY), 3150-3156, 3168-3172, 3206-3210, 3226-3232,  
 3244-3248, 3262-3268, 3318-3324, 3338-3344, 3360-3366, W/120 SHOTS, ACID  
 W/5250 GALS, 15% NE

PRODUCING INTERVAL: PERF (LANSING-KANSAS CITY) 3150-3366 GROSS,

OPER ADD: 125 NMARKET, STE 1720, WICHITA, KS, 67202 PHONE (316) 263-1201;

CONTR: RED TIGER DRLG

GEOL: RICHARD D PARKER

REISSUED TO ADD NEWLY RELEASED CONFIDENTIAL DATA. REPLACEMENT FOR CARD  
 ISSUED 6/11/91

IMAGED