

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10019-00-00
Spot: SENWNW Sec/Twnshp/Rge: 33-32S-42W
4030 feet from S Section Line, 4030 feet from E Section Line
Lease/Unit Name: KNOEBER A Well Number: 1
County: MORTON Total Vertical Depth: 3210 feet

Operator License No.: 5447
Op Name: OXY USA, INC.
Address: PO BOX 27570 5 E GREENWAY PLZ
HOUSTON, TX 77227

Production Casing Size: 5.5 feet: 3203 WITH 300 SX CMT
Surface Casing Size: 8.625 feet: 600 WITH 650 SX CMT

#104³³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/07/2004 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 600# HULLS & 25 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/07/2004 2:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 3172'. PERFS AT 3070-3108, 3023-30, 2996-3014, 2973-3014, & 2932-42'. 1ST PLUG PUMP 600# HULLS & 25 SX CMT & DISPLACE TO 2932'. 2ND PLUG LOAD HOLE WITH MUD. PUMP 50 SX CMT AT 650' THROUGH 5 1/2" CASING. 3RD PLUG PULL CASING TO 40'. FILL 8 5/8" TO SURFACE WITH 10 SX CMT.

RECEIVED
JAN 16 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 877' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
JAN 13 2004
KCC Dodge City

Signed

Steve Durrant
INVOICED (TECHNICIAN)

DATE 1-20-04
INV. NO. 2004061078