

RECEIVED

JAN 08 2004

Form CP-4

December 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

KCC WICHITA

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

Lease Operator: W.D. Short

Address: PO Box 729 - Oxford, KS 67119

Phone: (620) 455-3576 Operator License #: 6679

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12/29/2003 (Date)

by: Steve Van Gieson (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Stalnaker Depth to Top: 1866 Bottom: 1868 T.D. 2450

Stalnaker Depth to Top: 1900 Bottom: 1902 T.D. 2450

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 191-21289-001 <sup>60-01</sup>

Lease Name: Chamberlain

Well Number: 2

Spot Location (QQQQ): C - NE - SW - SW

990 Feet from  North /  South Section Line

1290 Feet from  East /  West Section Line

Sec. 21 Twp. 31 S. R. 2  East  West

County: Sumner

Date Well Completed: 8/11/1981

Plugging Commenced: 12/29/2003

Plugging Completed: 12/30/2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	300'	8 5/8"	300'	40'
Stalnaker	Oil	<del>surface</del> surface	2450'	4 1/2"	2450'	1370'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Shot 2 7/8 tubing off @ 1530' (1jt above packer stuck hole), placed 35 sax plug @ 1530', shot casing off @ 1370' (pulled casing)  
2jts 8 5/8" pulled with last joint of 4 1/2" casing, ran 10 joints 2 7/8" pumped 240 saxes (60/40 pos. w/4% jell),  
pulled tubing, ran 7jts 2 7/8" tag cement plug, pumped 275 saxes 60/40 pos w/4% jell, circulated to surface

Name of Plugging Contractor: W.D. Short License #: 6679

Address: PO Box 729 - 102 S. River Rd - Oxford, KS 67119

Name of Party Responsible for Plugging Fees: W.D. Short

State of Kansas County, Sumner, ss.

Don Short (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) W.D. Short

(Address) PO Box 729 Oxford, KS 67119

SUBSCRIBED and SWORN TO before me this 6 day of January, 2004

Denese A. Wilson My Commission Expires: 3/13/05  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 B