

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: WOOLSEY OPERATING COMPANY LLC
Address: 125 N. MARKET, SUITE 1000, WICHITA, KS 67202
Phone: (316) 267-4379 Operator License #: 33168
Type of Well: P&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 4/17/03 (Date)
by: DAVID P. WILLIAMS (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MISSISSIPPI Depth to Top: 4875 Bottom: 4902 T.D. _____
MISSISSIPPI Depth to Top: 4904 Bottom: 4914 T.D. _____
MISSISSIPPI Depth to Top: 4984' Bottom: 4990' T.D. 5094

API Number: 15-007-20472-00-01
Lease Name: HOLMES H
Well Number: 61
Spot Location (QQQQ): SENE - 5 - 34S - 13W
3300 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 5 Twp. 34 S. R. 13 East West
County: BARBER
Date Well Completed: 2/2/88
Plugging Commenced: 4/17/03
Plugging Completed: 4/21/03

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
<u>MISS 4866' TO 4990'</u>	<u>OIL & WTR</u>	<u>0</u>	<u>457'</u>	<u>8 5/8</u>	<u>457'</u>	<u>NONE</u>
		<u>0</u>	<u>5094'</u>	<u>4 1/2</u>	<u>5094'</u>	<u>3310'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SET CIBP @ 3750'. DUMP BAILER 2 SXS CMT ON PLUG. CMT AND PULL CSG (3313')
PUMP CMT PLUGS W/ 2 3/8" TBG . 10 SXS GEL & 40 SXS 60/40 POS CMT AT 600', 50 SXS CMT AT 470' AND 10 SXS CMT AT 60'
TOP OFF W/ READY MIX CMT.

Name of Plugging Contractor: CLARKE WELL SERVICE Corporation License #: 51605105
Address: MEDICINE LODGE, KS 67104
Name of Party Responsible for Plugging Fees: WOOLSEY OPERATING COMPANY LLC
State of KANSAS County, BARBER, ss.
RECEIVED
KANSAS CORPORATION COMMISSION
JAN 16 2004
CONSERVATION DIVISION
WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Carol W. D.
(Address) 1966 Roden Dr Medicine Lodge, KS 67104
SUBSCRIBED and SWORN TO before me this 3rd day of December, 2003
Charlotte C. Hoagland My Commission Expires: 8/2/04
Notary Public