

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21310-00-01
Spot: W2NWNWSE Sec/Twnshp/Rge: 6-6S-20W
2310 feet from S Section Line, 2530 feet from E Section Line
Lease/Unit Name: WALLGREN&MCC Well Number: 2
County: ROOKS Total Vertical Depth: 3496 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

Production Casing Size: 4.5 feet: 3494
Surface Casing Size: feet: 0
Surface Casing Size: 8.625 feet: 337 175 sxs cmt

113⁶²

Well Type: EOR UIC Docket No: E23628.1 Date/Time to Plug: 01/13/2004 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (308) 928-2221

Proposed Plugging Method: Ordered out 100 sxs 60/40 pozmix - 10% gel - 300# hulls.
2 7/8" tubing and packer set at 3124' - cemented to surface with 210 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2004 10:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Tied onto 2 7/8" - mixed and pumped 100 sxs cement with 200# hulls.
S.I.P. 300#. Annulus full of cement.

RECEIVED
JAN 22 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

ND

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 1-22-04
INV. NO. 2004061098

Form CP-2/3

JAN 14 2004

PETROLEUM MANAGEMENT, INC.
 400 N. WOODLAWN #201
 WICHITA, KS. 67208

#2 WALLGREN 6-6-20W
 330' FNL &
 110' FWL, SE/4

CONTR RED TIGER DRILLING CO. CTY. ROOKS

GEOL FIELD RAY EXT (1/8 s)

E 2102 KB CM 5/27/81 CARD ISSUED 8/6/81 IP P 30 BOPD
 ZU97 GL LKC 3236-3427 OA

API 15-163-21,310

+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
ANH	1578	+ 524	
B ANH	1610	+ 492	
*TARK	2882	- 780	
*TOP	2993	- 891	
OREAD	3147	-1045	
HEEB	3196	-1094	
TOR	3221	-1119	
LANS	3235	-1133	
RKC	3428	-1326	
GR WSH	3474	-1372	
GRAN	3476	-1374	
RTD	3496	-1394	
LTD	3498	-1396	
*SAMPLE TOPS			

8 5/8" 337/175sx; 4 1/2" 3494

DST (1) 3137-51/45-45-45-45, 15' OCM
 330' W, SIP 114-1097#, FP 27-90/
 117-171#

DST (2) 3186-3225/45-45-45-45, 20' M
 SIP 1586-1542#, FP 9-9/9-9#

DST (3) 3221-90/PKR FAILURE

DST (4) 3250-3315/45-45-45-45, 25' SOCM
 SIP 1604-1578#, FP 9-18/18-18#

MICT - CO, PF(LKC) 3236-40, AC250G,
 PF (LKC) 3423-27, AC4250G, SWB LD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

WALLGREN