

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22426-00-00
Spot: SESESW Sec/Twnshp/Rge: 6-6S-20W
330 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: WALLGREN Well Number: 4
County: ROOKS Total Vertical Depth: 3519 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: RR 1, BOX 28
PHILLIPSBURG, KS 67661

Production Casing Size: 4.5 feet: 3516 125 SX CMT
Surface Casing Size: 8.625 feet: 359 250 SX CMT

11437

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/13/2004 10:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JASON BACH Company: BACH OIL PRODUCTION Phone: (308) 928-2221

Proposed Plugging Method: Ordered out 175 sxs 60/40 pozmix - 10% gel - 14 sxs gel - 500# hulls.
DV set at 1622' w/365 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/13/2004 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 4 1/2" - mixed and pumped 25 sxs cement with 200# hulls,
followed with 14 sxs gel and topped with 100 sxs cement with 300# hulls.
Max. P.S.I. 1250#. S.I.P. 300#.
Annulus full of cement.

RECEIVED
JAN 22 2004
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed _____

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE

1-22-04

INV. NO.

2004061098

JAN 14 2004

PETROLEUM MANAGEMENT, INC.
400 N. WOODLAWN, #201
WICHITA, KS 67208


#4 WALLGREN

6-6-20W
SE SE SW

CONTR RED TIGER DRILLING CO. CTY ROOKS

GEOLOGIST GREG WILLIAMS FIELD RAY

ELV 2125 KB SPD 7/23/84 CARD ISSUED 3/14/85 IP P 21 BO & 14 BWPD
DRLG COMP 7/30/84 LKC 3252-3275 UA



LOG	Tops	Depth Datum	API 15-163-22,426
B/FT HAYS	287+	1838	8 5/8 " 359 / 250SX, 4 1/2 " 3516 / 125SX NO CORES
SC	1618+	507	DST (1) 3066-3090 (TOP, DR CR) / 45-45-45-45, WB & INCRG, REC 80' MW, SIP 1047-1006#, FP 66-81 / 99-110#
B/SC	1649+	476	DST (2) 3177-3200 (OREAD) / 45-45-45-45, WB & INCRG, 260' OIL SPTD MW, SIP 1122-1091#, FP 71-99 / 146-170#
TOP	3016-	891	DST (3) 3226-3262 (HEEB, TCR) / 45-45-60-60, WB & INCRG, 60' GIP, REC 125' GSY MCO, SIP 537-527#, FP 81-88 / 96- 112#
DR CR	3074-	949	DST (4) 3258-3280 (TOR, LANS) / 45-45-30-45, WB & DECRG, REC 30' RM, PRESSURES NA
OREAD	3179-	1054	MICT - CO, PF (LKC) 3252-55, AC 2000G, SWB LD, GSO, PF (LKC) 3270-75, AC 250G, SWB DWN, GSO, T&R, POP, P 21 BO & 14 BWPD (GR 39%), 8/23/84
HEEB	3228-	1103	
TOR	3250-	1125	
LANS	3267-	1142	
BKC	3460-	1335	
MARM	3484-	1359	
GRAN	3506-	1381	
RTD	3519-	1394	

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

MAOICEP